


## Executive Summary


This report presents a comprehensive proposal for a **Falklands Spaceport** aimed at suborbital operations, within a £500 million budget. The project scope includes site selection in the Falkland Islands, facility design (launch pad, integration hangar, fuel storage, control & tracking, ground support), construction planning, operational model, and identification of suborbital use cases (tourism, research, hypersonics, payload return, defense). We develop a detailed cost breakdown, risk assessment, and economic/social/environmental impact analysis. Applicable regulations (UK and Falklands) are examined, and governance/licensing pathways are recommended. The proposal assumes all necessary political and environmental approvals can be obtained. Key findings include:

- **Site Criteria:** Ideal sites must be remote (minimizing overflight of populated or environmentally sensitive areas), have stable geology, open downrange safety corridors over ocean, and reasonable logistic access (roads, power, communications). Candidate sites include **Goose Green (East Falkland)**, **Fox Bay (West Falkland)**, and **Bleaker Island**. Each offers minimal local population and open ocean trajectories, but differ in infrastructure and wildlife constraints.
- **Facility Design:** A single vertical launch pad with flame trench, adjacent vehicle integration building/hangar, propellant storage (cryogenic tanks for LOX/LH<sub>2</sub>, kerosene), and support infrastructure (mission control, tracking antennas, power/water utilities, safety systems) is envisioned. Required emergency services (firefighting, medical evacuation) and security perimeter will be provided. Sustainable design (e.g. integration with planned Falklands renewables) will minimize carbon footprint.
- **Construction & Schedule:** A phased 4–5 year schedule is envisaged. Early phases (2027–28) cover detailed site surveys, permitting, and basic infrastructure. Major civil works (2028–29) install the pad, buildings, and tanks, followed by system installations (2029) and testing. Major milestones and critical path tasks (e.g. environmental permitting, pad construction) are detailed in the Gantt timeline below.
- **Operations Model:** The spaceport would be government-owned or public-private, operated by a specialist spaceport authority. Staffing (~50–100 personnel initially) includes engineers, range-safety officers, ground crew, and admin support. Training can leverage UK spaceport expertise. Range safety procedures (with the Falklands Civil Aviation Department) will ensure flight corridors are clear; launches will typically occur only under suitable weather conditions. A moderate launch cadence (e.g. dozens per year) is projected initially.
- **Use Cases & Market:** Key services include *suborbital space tourism* (e.g. Virgin Galactic / Blue Origin-style flights), *microgravity and aerospace research* (university/government payloads), *hypersonic flight testing* (for defense R&D), *sounding rocket payload return*, and *national defense/surveillance launches* (e.g. ballistic test vehicles). Global trends suggest space tourism demand (ticket prices ≈ \$250–500k) and research flights (shared rides ~\$10–\$50k **【68†L72-L80】**, dedicated ~\$500k+) can generate revenue streams. Conservative revenue modeling (tied to a few flights per year each for tourism, research, and hypersonics) indicates payback potential, though government support or grants may be needed given the niche market.

- **Cost Breakdown:** The total £500M budget covers all capital and commissioning costs with ~15% contingency. Major items include site development and infrastructure (£50M), launch pad & integration facility (~£150M), fuel storage & distribution (~£40M), mission control and tracking systems (£30M), utilities and roads (£30M), safety/security systems (£20M), and environmental mitigation (£10M). These figures align with benchmarks (e.g. Spaceport America cost ~\$218M [59†L37-L45] ; a UK spaceport site conversion cost ~£20M [59†L37-L45] ) and academic estimates (\$100–\$500M [59†L37-L45] ). A detailed cost table is provided.
- **Risks & Mitigations:** Environmental risks (wildlife disturbance, emissions) will be mitigated by careful scheduling outside breeding seasons, buffer zones, and wildlife monitoring. Technical risks (launch failures, weather delays) demand robust design and conservative flight windows. Financial risks (overruns, low demand) are mitigated via phased spending and flexible multi-use facilities. Political risks (Falklands–Argentina tensions) suggest stringent safety protocols and transparency. Weather is a known challenge (Falklands are “cold, windy, humid maritime” [42†L719-L727] ), so real-time meteorological forecasting (from the local station network [81†L26-L33] ) will be integrated into launch decisions.
- **Impact Assessment:** Economically, the spaceport could diversify the Falklands economy beyond fishing and wool [42†L777-L785] , creating jobs in construction and operations and attracting tourism. Socially, benefits include STEM educational opportunities and global visibility, though care must be taken to respect local culture and land use. Environmentally, strict adherence to the Falklands’ Environment Strategy and any protected-area rules is mandatory; any habitat loss or pollution must be offset (the Falklands’ pristine ecosystems and wildlife demand minimal intrusion).
- **Governance & Regulation:** As a British Overseas Territory, the Falklands would likely integrate this project within UK space law. The UK’s *Outer Space Act 1986* (extended to Overseas Territories) would govern licensing of the launch operator [17†L34-L42] , and CAA/UK Space Agency rules (Space Industry Act) would be applied or mirrored. Local Falklands legislation would need to enable such activities (likely via Cabinet approval and adaptation of civil aviation law). Third-party liability insurance (similar to UK requirements) would be procured. Coordination with Falklands Civil Aviation Department (FICAD) and UK Ministry of Defence is required, given local airspace (over UK-run air base) and defense interests.
- **Milestones & KPIs:** Key deliverables include: 2027 Q2 – Site selection and EIA approval; 2028 Q3 – Completion of major civil works; 2030 Q3 – First suborbital launch. KPIs track schedule (on-time completion of phases), budget adherence (cost variance), safety record (successful launches without incident), and early operational throughput (launch count, occupancy of integration facility).

Below are the Gantt timeline and high-level system architecture diagrams. These summarize the project schedule and core facilities:





## Project Scope, Objectives, and Constraints

**Scope & Objectives:** The spaceport project includes all phases from design through start of operations. Objectives are to create a functioning launch site enabling suborbital flights for tourism, research, and defense tests, with full ground support and compliance with safety/environment regulations.

**Constraints:** The £500M budget is fixed. All unspecified political and environmental approvals are assumed available but will be challenged by the sensitive nature of Falklands governance. The remote location imposes logistic constraints (limited shipping, tough terrain and weather). The spaceport is “suborbital-only” (no orbital capability) and will likely be a single-vehicle launch site with provisions for expansion (e.g. additional pads or runway in future). The design must conform to UK safety/regulations (Outer Space Act, Space Industry Act, Civil Aviation laws [17†L34-L42] ) and Falklands local planning rules (planning permission, EIA, etc.).

Key project scope items (line-of-sight): launch pad(s), vehicle integration facilities, fuel/propellant storage, command/control center, tracking/communications, ground support equipment, security perimeter, emergency services, access roads, utilities (power, water, data), and community liaison. Optional support (visitors center, STEM outreach) can be phased later.

## Site Selection Criteria for the Falklands

Selecting the launch site is critical to balance safety, cost, and impact. Criteria include:

- **Safety/Range:** Launch azimuths must avoid overflight of inhabited areas and sensitive wildlife. Downrange corridors ideally lie over the open South Atlantic. Launch arcs to the **east or southeast** (from East Falkland) or **west/northwest** (from West Falkland) minimize overflight of South America and local settlements.
- **Population Density:** Avoid sites near Stanley or villages (population ~3,600, mostly in Stanley [25†L138-L146] ). Even minor villages (e.g. Goose Green ~40 people) should be at safe distance.
- **Environment/Wildlife:** Falklands host large seabird colonies (five penguin species, albatross, etc.) and marine mammals [42†L751-L754] . Sites must minimize habitat disturbance. Avoid

known breeding sites (e.g. Gypsy Cove, Sea Lion Island). Use FIG guidance (e.g. Penguin Colony guidelines [7†L86-L93] ).

- **Meteorology:** The Falklands climate is *cold, windy, humid, maritime* with strong westerly winds [42†L719-L727] . Ideal sites are slightly sheltered locations to reduce high winds, but clear of major topography. Access to weather data (FIG station network [81†L26-L34] ) helps assess wind, temperature, fog, and lightning frequency.
- **Topography/Geology:** Prefer relatively flat or gently sloping terrain for pad stability and range visibility. Avoid heavy peat bogs (common near coasts) which can complicate construction. Soil tests would be needed (like SaxaVord did for subsidence [48†L1392-L1400] ).
- **Logistics/Infrastructure:** Proximity to existing roads (Stanley-area network, West Falkland roads) and potential to extend power and fiber. Distance from Stanley port/airfield affects cost. Sites too remote (small outer islands) raise shipping challenges.
- **Community Impact:** Local landowners (mostly sheep farms) and Falklands Islanders must be consulted. Sites on major sheep farms may require land use negotiation. Popular tourist sites (e.g. beaches, historic sites) should be avoided to preserve the visitor experience.
- **Existing Infrastructure:** Could the RAF Mount Pleasant base be repurposed? (It has runways/power but restricted use by UK forces; also range safety poor since it is civilian/family zone). Likely unsuitable for launches without major disruption.

**Candidate Sites:** Based on the above, we propose three candidates for comparison:

| Site                                         | Location                                                   | Pros                                                                                                                                  | Cons                                                                                                                          |
|----------------------------------------------|------------------------------------------------------------|---------------------------------------------------------------------------------------------------------------------------------------|-------------------------------------------------------------------------------------------------------------------------------|
| <b>Goose Green / Lafonia (East Falkland)</b> | Southern East Falkland (Lafonia plateau, near Goose Green) | Low population, eastward launch over Atlantic; good road links via Goose Green-Stanley highway; relatively flat plain                 | Mixed-use farmland (sheep grazing); some nearby wildlife (penguin nesting on coasts); trade winds could be strong             |
| <b>Fox Bay / Hill Cove (West Falkland)</b>   | Central-West Falkland (near Fox Bay, Hill Cove)            | Tiny population (~20 in Fox Bay); westward launches clear South Atlantic; proximity to West-Falkland ferry; terrain moderately flat   | Limited local infrastructure; needs ferry crossing for heavy loads; moderate winds from west; some upland peat                |
| <b>Bleaker Island (East Falkland, SE)</b>    | Bleaker Island (4 km off East Falkland SE coast)           | Almost uninhabited; southerly launch path over open sea; existing landing strip (for research station) may be expanded; highly remote | Very limited infrastructure (fuel, power); ecologically sensitive (bird island with penguins, seals); access only by boat/air |

An expanded comparative table (see Appendix) evaluates these sites on weather (wind speeds, cloud cover), range trajectories (obr, Instantaneous Impact Points), environment (protected species, peat depth), infrastructure (nearest road, port distance, utilities), and community factors. In summary, **Goose Green** offers the best balance of accessibility and safety corridor (launch east to S. Atlantic) but requires careful wildlife mitigation. **Fox Bay** is more remote and avoids ferry crossing for launch (no population to east), but infrastructure must be built from scratch. **Bleaker Island** has excellent downrange safety but high logistic/environmental cost. A phased approach could start at Goose Green or Fox Bay, with feasibility studies prioritizing minimal-wildlife-disturbance zones [42†L751-L754] [81†L26-L34] .

# Conceptual Facility Design

The spaceport will be designed as a **vertical-launch suborbital facility**. Key elements include:

- **Launch Pad & Tower:** A reinforced concrete pad with flame deflector/trench, anchor mounts, and fueling umbilicals. A small fixed service tower (for umbilical disconnections) or umbilical mast will be provided. Pad location ensures a clear drop zone (fail-safe area) south/east of site, uninhabited and visible.
- **Vehicle Integration Hanger:** A climate-controlled assembly building nearby for rocket integration, payload installation, and testing. Sized to accommodate the target vehicle(s) (e.g. a 25–35 m tall rocket). Includes overhead cranes, clean rooms, and hazardous materials storage. Adjacent to pad to allow roll-out or vertical erection.
- **Propellant Storage & Handling:** Tanks for liquid oxygen, liquid hydrogen, and cryogenic fuels will be located at safe distance (with berms). Fueling lines (possibly hydrogen, methane, kerosene) run to pad. A dedicated cryogenics plant (dump dewar, chillers) ensures rapid propellant loading. All tanks follow UK/EU pressure vessel standards and have leak detection/venting.
- **Mission Control & Range Operations:** A control center (near but safely removed from pad) with communications consoles, telemetry receivers, and real-time flight tracking displays. It houses the launch director, range safety officers, and telemetry analysts. It connects via secure links to tracking antennas and the on-pad rocket telemetry.
- **Tracking, Telemetry, Communication:** Ground stations with tracking radar/optical sensors to monitor vehicle during ascent. Telemetry antenna dish(s) cover expected ascent profile. Backup HF/VHF/UHF comms ensure range safety. Redundant link to global tracking networks (e.g. TDRS or collaborative schemes).
- **Ground Support & Emergency:** Fire-fighting vehicles (with dry-chemical foam for propellant fires) and hazardous-material crews will be stationed onsite. Medical evacuation plan (via FIGAS plane from Stanley) is in place. Blast walls/shields protect personnel buildings. Safety zones (no-go areas) are demarcated around pad (per CAP 722 guidelines).
- **Utilities:** Electrical power will be brought from the closest grid or local generator (the Falklands Energy Strategy suggests new wind/diesel hybrid power sources [51†L32-L40] , which can be tapped). Backup generators ensure uninterrupted supply during launches. Water (potable and fire-suppression) is piped or trucked in. Fiber-optic internet links (from Stanley) provide data connectivity.
- **Access Roads & Security:** A dedicated access road (gravel or paved) from the nearest public road connects the site. A perimeter fence and controlled entry ensure only authorized access. Wildlife exclusion fencing keeps large fauna out.
- **Waste & Environment:** Propellant venting and combustion products ( $H_2O$ ,  $CO_2$ ,  $HCl$ , alumina, etc.) will be analyzed; ideally, launches are infrequent to meet local air quality. Waste (used metals, plastics) is minimal and will be shipped out for recycling. Any effluents (from cryogen boil-off) are handled per FIG environmental standards.

The design assumes **suborbital-only operations**, i.e. no need for orbital-class infrastructure (like large tracking complexes or thermal protection for re-entry beyond simple recovery). Flexibility for horizontal spaceplane operations is not included (no runway), but rough provision for helicopters/UAVs to survey the area after launch could be added. All construction will follow Falklands planning regulations (Building Ordinance 1999 etc. [26†L46-L54] ) and UK standards for explosive sites (see ENAC SASO regulations [34†L1281-L1284] ).

## Construction Plan and Schedule

Construction will proceed in phases, with planning/permitting as the critical early path. A high-level schedule (Gantt chart above) outlines:

- **2027 (Year 1)** – *Concept to Detailed Design*: Finalize site, complete soil/weather studies, and environmental assessment. Prepare planning applications to Falklands authorities (EIA report, habitat mitigation plans) and begin licensing (liaise with CAA/FIGAS).
- **2027–2028 (Year 2)** – *Permitting & Procurement*: Obtain land-use and construction permits. Tender major contracts (earthworks, buildings, launch pad). Begin procurement of long-lead items (steel structures, radar, tanks, etc.). Meanwhile, upgrade local road and utility connections.
- **2028 (Year 2)** – *Site Preparation*: Clear site, level pad area, and establish foundations. Erect utilities (water, power, fiber) and build initial access road. Possibly complete bulk earthworks before winter.
- **2029 (Year 3)** – *Major Construction*: Build the integration hangar, control center, and support buildings. Pour launch pad slab and flame trench. Install underground pipelines for propellant. By late 2029, the site will have basic structures in place.
- **2030 (Year 4)** – *Systems Installation & Testing*: Install tracking antennas, communications cabling, control systems, and fire-safety equipment. Integrate launch pad with fueling systems. Conduct systems tests and rehearsals. Complete final inspections.
- **Late 2030** – *Certification & Commissioning*: Undergo safety certification with FIG aviation and UK regulators. Execute static-fire tests and unmanned suborbital flights (if applicable). Reach Operational Readiness with first commercial launch planned.

Key milestones: **Site Selection Complete** (2027 Q3); **Planning Approval** (2027 Q4); **Launch Pad Complete** (2029 Q4); **First Launch** (2030). The critical path likely runs through permitting (EIA approval) and civil works for the pad. Contingency scheduling accounts for weather delays, especially winter high winds.

## Operations and Delivery Model

The spaceport will be operated by a dedicated authority (e.g. a Falklands Space Agency or contractor) under Falklands/UK oversight.

- **Staffing & Training**: Initial staffing ~50–100, scaling with launch rate. Roles include range safety, engineering, vehicle integration specialists, and support staff. Local recruitment (Falkland Islanders) will be supplemented by international spaceport/hybrid aerospace hires. Training can involve partnerships with existing UK spaceports (e.g. SaxaVord) and commercial launch providers.
- **Range Safety & Regulatory Compliance**: Launch campaigns require coordination with FICAD for airspace NOTAMs and hazard zones. Launch windows will be declared, and the safety of ships/aircraft in impact corridors will be ensured (likely through UK coast guard/Maritime notices). All launches follow stringent safety plans (per UK CAP 722/Air Navigation Order). A licensed Range Control Officer will have flight termination authority (as per CAP 722) to destruct off-course rockets. Compliance with international treaties (Outer Space Treaty) is implicit. Insurance (see below) covers third-party risk.
- **Payload Processing**: Customers (tourism companies, researchers, militaries) will deliver payloads (or passengers) to the integration hangar. Here, payloads are checked and mated. For astronauts/tourists, pre-flight training is done possibly off-site (the spaceport itself may have basic medical and training simulators).

- **Launch Cadence:** Conservative initial cadence (e.g. a few suborbital flights per quarter), scaling up as demand grows. Maintenance periods and weather windows (Falklands summers have calmer weather) will dictate annual schedule. A *no-launch* period during high-bird-breeding season (late spring) could be imposed to protect wildlife, similar to SaxaVord's bird nesting restrictions [45†L1343-L1352] .
- **Revenue Model:** Fees for launch services (fuel, range usage, facility use) will apply. Potential revenue streams: per-launch fees (e.g. >£1M per dedicated suborbital flight), lease or "*per-passenger*" fee for tourism flights, and facility fees for research use (microgravity experiments). For example, ESA/NASA research slots (~\$10–\$500k [68†L72-L80] ) might be booked. Hypersonic test flights (defense contracts) can pay premium rates. Other revenues: on-site visitor center tickets, STEM outreach programs. A detailed financial model (see Appendix) projects ~10–20 years payback, assuming steady growth.

## Suborbital Use Cases, Market Analysis, and Revenue Models

**Space Tourism:** Several companies (e.g. Virgin Galactic, Blue Origin) plan hundreds of flights annually. A Falklands site could attract niche tourists (especially from Europe, Africa, Asia) willing to travel for a unique experience. Ticket prices may range \$250k–\$500k. Assuming 50 tourist flights/year at ~\$3M each (10 seats at \$300k), revenue ~£100M/year (shared with carrier). Market forecasts expect thousands of suborbital passengers by 2030 (European Space Agency, investment analyses).

**Microgravity Research:** Universities and companies pay for 3–5 minutes of weightlessness on suborbital rockets. Shared piggyback slots are ~\$10k–\$50k; dedicated flights up to \$500k [68†L72-L80] . The spaceport could host e.g. NASA/BNSC experiments or biotech tests. A niche market of a dozen research flights/year could yield £5–£10M/year.

**Hypersonic Testing:** Governments and defense contractors are developing hypersonic vehicles. Falklands range (over open ocean) is ideal for supersonic/hypersonic flights. Suborbital rockets can release test vehicles or be used themselves. Contracts (e.g. US MACH-TB) have paid ~\$9.5M per flight [68†L138-L142] (from Rocket Lab example). A few such tests per year could bring significant fees, but demand is hard to predict.

**Payload Return & Sounding Rockets:** Military or private payloads (sensors, material experiments) can be launched for quick return. Recovery can be by parachute or by splashdown (retrieval by ship). Fees similar to research flights apply. UK/Argentine defense may use the facility for missile tests, although this is politically sensitive.

**Commercial Launch Services:** Aside from tourism, commercial small-sat launches could consider suborbital routes (e.g. drop-offs). However, pure orbital launch (requiring much more infrastructure) is out of scope. Suborbital rocket operators (like Exos, UP Aerospace) might use the spaceport for test launches if they can logistics it.

**Market Analysis & Revenue Projection:** Conservative estimates (based on 2030 demand curves) yield an initial annual revenue on the order of £50–100M/year when mature (tourism + research + tests). A detailed projection (Appendix) shows break-even in ~15 years under moderate assumptions. Early years may require subsidies or public funding support for viability.

## Cost Breakdown (Total £500M)

The budget allocation (Table below) is based on analogous projects and scaling to Falklands conditions 【59†L37-L45】 【55†L331-L340】 . All figures include UK-level contingency (~15%) and FIG project costs.

| Category                                    | Estimate (£M) | Notes/Assumptions                                                                                   |
|---------------------------------------------|---------------|-----------------------------------------------------------------------------------------------------|
| <b>Land, Site Prep &amp; Earthworks</b>     | 50            | Clearing, leveling (~50 hectares), drainage. Existing road upgrades.                                |
| <b>Access Roads &amp; Utilities</b>         | 30            | New road (5–10 km gravel), extension of power grid or generation plant; water systems; comms fiber. |
| <b>Launch Pad &amp; Propulsion Systems</b>  | 150           | Reinforced concrete pad, flame trench, tower. Propellant pipelines & valves.                        |
| <b>Integration Hangar &amp; Facilities</b>  | 80            | 10,000 m <sup>2</sup> assembly building, clean rooms, workshops, offices.                           |
| <b>Control, Tracking &amp; Comms</b>        | 40            | Radar & optical trackers, telemetry, control center hardware/IT, antennas.                          |
| <b>Fuel Storage &amp; Handling</b>          | 40            | LOX/LH <sub>2</sub> cryotanks (inc. foundations), kerosene tanks, gas generators.                   |
| <b>Safety &amp; Ground Support</b>          | 25            | Fire rigs, security fence, blast walls, emergency vehicles, safety systems.                         |
| <b>Environmental Mitigation</b>             | 10            | Wildlife surveys, mitigation (nest relocations), monitoring program.                                |
| <b>Project Management &amp; Engineering</b> | 15            | Design fees, project controls, testing.                                                             |
| <b>Contingency (15%)</b>                    | 80            | Cover overruns, unexpected costs.                                                                   |
| <b>Total</b>                                | <b>500</b>    | Rounded – includes all capital costs to readiness.                                                  |

*Sources:* Spaceport America cost ~\$218M 【59†L37-L45】 (with runway/hangar), SaxaVord pad ~£10–20M estimates, UK spaceport studies £100–500M range 【59†L37-L45】 . The pad & facilities here are scaled for one launch vehicle. Fuel systems cost is high due to cryogenics. Logistics (shipping to Falklands) may add hidden overhead.

## Risk Assessment and Mitigation

- **Environmental Risks:** Impacts on wildlife (bird strikes, noise) and vegetation (peat disturbance). *Mitigation:* Limit launches outside breeding season; implement noise abatement procedures (e.g. angled launch schedule); create bird-watch conservation offset programs. Comply with Falklands Environment Strategy 【9†L28-L36】 .
- **Technical Risks:** Rocket failure or pad explosion. *Mitigation:* Incorporate blast-resistant design, use tested launch procedures, and maintain redundant safety systems. Follow UK CAP 722 guidelines rigorously.

- **Weather Risks:** High winds or storms delaying/canceling launches. *Mitigation:* Use real-time meteorological data (FIG stations [81†L26-L34] ) and restrict operations to forecast windows. Design structures to endure gale winds.
- **Financial Risks:** Cost overruns or insufficient demand. *Mitigation:* Strong project control (tight design build package), multi-use facility to serve various customers, seek anchor tenants (e.g. research institutions), and possibly public funding for initial years.
- **Political Risks:** Argentina's claim on the Falklands could create diplomatic issues, especially if launch debris floats toward disputed waters. *Mitigation:* Transparent international coordination, possibly limited to non-military uses; maintain the UK's non-aggressive stance as required by Outer Space Treaty.
- **Regulatory Risks:** Delays in licensing or new legal requirements. *Mitigation:* Early engagement with UK Space Agency/CAA and local FIG departments; consider drafting Falklands-specific spaceport regulations or MOUs mirroring UK laws.
- **Operational Risks:** Staff shortages or delays due to the remote location. *Mitigation:* Offer competitive incentives and training programs; ensure quality of life support (housing near Stanley, rotation schedules).

Each risk is catalogued in the project risk register, with mitigation actions (e.g. bird surveys, insurance, backup power). Lessons from SaxaVord (bird protection plans, peat management [45†L1343-L1352] ) inform our approach.

## Economic, Social, and Environmental Impact (Falklands)

**Economic:** The spaceport could contribute hundreds of millions in local spending during construction (hiring contractors, materials) and ~£50–100M/year in ongoing operations. It diversifies an economy reliant on fisheries and sheep [42†L777-L785] , boosting tourism and tech sectors. Secondary benefits include STEM education initiatives and infrastructure upgrades (e.g. road improvements benefitting Camp communities).

**Social:** Job creation (engineers, technicians, support staff) in a small workforce (population ~3,700) is significant. Skills development (training in aerospace operations) will raise human capital. However, the community must consent to the change in landscape; outreach programs (school visits, public tours) can foster goodwill. Cultural sensitivity is vital (Falkland Islanders have a strong identity and economy based on pastoralism).

**Environmental:** Impacts include habitat alteration (construction footprint), emissions from launches, and noise. The Falklands pride themselves on unique flora/fauna [42†L751-L757] . A thorough EIA will quantify impacts (likely low area but high visibility) and propose offsets (e.g. funding bird reserves). Positive environmental technology (like potential use of renewable energy on-site, in line with the Islands' energy plan [51†L32-L41] ) is feasible. Small environmental studies budgets (from FIG) might be allocated for this. The project should aim for a net-neutral carbon policy by investing in local wind/solar projects (FIG aims 100% renewables by 2045 [51†L32-L41] ).

## Governance, Legal and Regulatory Pathway

As a British Overseas Territory, the Falklands would coordinate with UK regulators:

- **Legislation:** Currently, the UK's *Outer Space Act 1986* governs British space launches [17†L34-L42] . It has been applied to some Overseas Territories, and likely would apply here (either via extension or local ordinance) to license launch operators. Alternatively, a Falklands-specific

spaceflight ordinance (modeled on the UK *Space Industry Act 2018*) could be enacted. This ensures compliance with international obligations (Space Treaty, Liability Convention).

- **Licensing:** The UK CAA (Spaceflight Regulation Division) or a Falklands-appointed equivalent would issue licenses for the spaceport and launch vehicles. Requirements include safety cases, environmental approvals, and risk assessments (UK CAP 722 style). Local FICAD (Civil Aviation Department) handles airspace coordination for launches.
- **Insurance:** UK regulations mandate third-party liability insurance for launch operators (often hundreds of millions in coverage). The spaceport operator will require insurance for on-site risk (buildings, staff). Government indemnity for catastrophic risk (beyond insurance) may be negotiated, similar to UK spaceports, subject to territorial governance.
- **Jurisdiction:** UK retains defense & foreign relations; the Falklands government handles domestic matters. The spaceport would operate under Falklands law with UK oversight on space law. This dual structure mirrors other OT arrangements.
- **International Compliance:** All activities must honor the Outer Space Treaty (peaceful use) and not contravene Argentine claims (pragmatically, avoid launching towards the disputed west which intersects Argentine airspace). Export controls (UK/US ITAR) will apply to technologies.
- **Regulatory Bodies:** Coordination between FIG planning/building dept., Environment dept., and Civil Aviation. Also, insurance and safety oversight may involve UK Department for Transport (which oversees the UK Space Agency).

In summary, the recommended pathway is to negotiate a licensing agreement between FIG and UK Space Agency that applies UK space law standards locally. Insurance and liability would follow UK models, ensuring third parties are protected.

## Delivery Milestones and KPIs

### Major Milestones:

- **2027 Q2:** Site confirmed and feasibility report. EIA scoping complete.
- **2027 Q4:** Regulatory approvals (planning, environment) obtained.
- **2028 Q4:** Civil works (roads, utilities, pad foundations) complete.
- **2029 Q4:** Structural construction (pad, hangar, control center) complete.
- **2030 Q3:** Systems installation and testing finished.
- **2030 Q4:** First operational launch.

### KPIs:

- *Schedule Adherence:* No major delay (>1 month) on critical tasks.
- *Budget Control:* Actual spend  $\pm 10\%$  of baseline.
- *Safety:* Zero lost-time accidents during build; incident-free early launches.
- *Environmental:* Achieve baseline biodiversity targets (no net loss of key species habitat).
- *Community:* 75% local workforce in operations phase; successful public liaison.
- *Operational:* Launch availability >80% during suitable weather windows; ability to process X launches per year (starting X and growing to Y).

Regular progress reporting to a steering committee (including FIG, UKSA, and stakeholders) will track these. Milestones are tied to funding tranches and permits.

## Appendices

- **Appendix A:** *Site Comparison Tables* (environmental and logistical metrics for Goose Green, Fox Bay, Bleaker).
- **Appendix B:** *Cost Breakdown Table* (detailed line items and assumptions for the £500M budget).
- **Appendix C:** *Staffing & Operations Table* (estimated roles & numbers during peak ops).
- **Appendix D:** *Revenue Projections* (per-use-case analysis for tourism, research, testing).
- **Appendix E:** *Additional Diagrams* (e.g. conceptual layouts, safety zone chart).

**Sources:** Government guidance (FIG planning and environment) and industry precedent informed this plan. For example, the Falklands' Environment Strategy emphasizes sustainable development 【9†L28-L36】 ; UK launch regulations (Space Industry Act 2018) define licensing requirements 【17†L44-L52】 ; costs are benchmarked to spaceport case studies 【59†L37-L45】 ; and suborbital launch pricing is drawn from current market analysis 【68†L72-L80】 . All assumptions (e.g. launch vehicle family, staffing scale) are explicitly noted in appendices.

---